




Silicon Closeout Goals

- ◆ Build 15 staves between now and Feb. 03.
- ◆ Assemble L0 modules (~5) on CF structure
- ◆ Assemble Staves and L0 into “barrel” and test through April 03
- ◆ Write NIM article(s) on Run IIb Silicon design and prototype results
- ◆ Finish End of April 2004

- ◆ Remaining Closeout Total Cost
- ◆ WBS schedule
 - ➔ M&S
 - ~ 100k\$ left to spend (inc. OH)
 - ➔ Labor ~ 296k\$ + 90k\$ OH





Recent Successes

- ◆ 7 presentations at IEEE/NSS Oct. 03 Portland, OR
 - ➔ Stave Design and testing
 - ➔ Deadtimeless operation of the staves
 - ➔ L0 design and testing results
 - ➔ Comparison of BeO and Polyimide MPCs
 - ➔ Performance of the RunIIb Silicon sensors
 - ➔ Run IIb Silicon DAQ upgrades and development of simple test system
 - ➔ SVX4 chip
- ◆ We are currently in the process of writing up these for publications in IEEE transactions.



Hybrid Assembly




LBL/Davis workshop July 03

- ◆ Hybrid “preproduction” at LBL and Davis
 - ➔ Oversight of assembly and testing expertise provided by LBL, INFN, Helsinki, all at LBL
 - ➔ hybrids “stuffed” at two different assembly houses and wirebonded at a separate factory (promex)
 - ➔ Tested and encapsulated at LBL
 - ➔ Shipped to Davis for Burnin
 - ➔ Burnin at Davis – results evaluated, entered in database
 - ➔ Ship good ones to FNAL, bad ones back to LBL




Part Counts

- ◆ 90 hybrids assembled between mid Sept and mid Oct
- ◆ 61 hybrids passed burn-in at UC Davis
 - ➔ 16 more have been burned in
 - ➔ Expect to ship to FNAL this week




- ◆ BeO Mini- PC received last month
 - ➔ 4 assembled so far
 - ➔ They work well
 - production problems with prototypes solved by vendor
 - 0.25 micron transceiver chips work as planned!
 - ➔ 2 have been glued to stave cores





Modules and Staves

- **15 Modules Oct. 8-27**
 - new hybrids
 - new SVX4 chips
 - production sensors
 - pitch adapters
 - fixturing
- **1st half stave completed Oct. 31**
- **2nd stave to be started this week**



**Module –Module misalignment
Average = 1.5 microns!**




Bulkheads



Outer Bulkhead

- staves installed through slots
- pins provide precise alignment




Inner bulkhead ($z=0$)

- installation arm passes through holes
- pins provide precise alignment



Bulkhead Assembly


Precision of pin locations is built into assembly plates



1/3 of pins are glued at a time



Barrel Test and Display Box



- ◆ Supports outer barrel from mounts on bulkheads
- ◆ Supports L0 and hybrids on a separate pipe
- ◆ cooling and cables will be dressed to cross bars
- ◆ Walls will be dark for testing
- ◆ can be replaced by plexiglass for display purposes



Bulkhead Status

- ◆ Pin gluing fixture used to install all pins in both inner and outer bulkheads
- ◆ Measurements of pin locations finished last week
- ◆ Analysis of data in progress


- ◆ These bulkheads will be used to build a barrel
- ◆ Design of testing/display box completed – now in drafting



Test with prototype staves


- ◆ Shine laser light on stave
- ◆ See clear and clean signal after pedestal subtraction

Laser signal with Offline Pedestal Subtraction





Unique aspect of Stave: Compact Design




- ◆ Hybrids glued to sensors
- ◆ **Sensors in proximity of bus cable:** crucial feature, very attractive mechanically, but challenging for electrical performance
- ◆ 3 separated aluminum shield sections
- ◆ bus cable traces stop after reaching 3rd hybrid
- ◆ Can study and compare noise in 1st two modules to 3rd module
- ◆ Can study different shield and ground configurations



Tests with prototype staves: Best so far

- ◆ Pedestal level and noise for an arbitrary channel over all modes of chip operation
- ◆ pedestal shifts are largely suppressed remaining effects are typically less than the equivalent of a Minimum Ionizing Particle (MIP)
- ◆ shifts are completely gone when using real-time pedestal subtraction (RTPS), which removes “average” pedestal event-by-event





Stave Shield Studies

Without shield (red, left axis):

huge pickup effects due to control signal single-ended lines: fast rise times couple effectively to back plane.


This pickup only occurs on channels directly over the control lines of the bus cable

With shield (purple, right axis):

coupling to sensor strongly suppressed

Other tools to reduce pickup:

- select slow preamp rise time
- optimize control patterns:
e.g. raise signals outside of preamp integration time






L0 Modules and Hybrid on CF

Sensors Module 1

Cables (Dyconex)

CF support


Hybrid



**Module 2 sensors and Keycom cables underneath
Module 1 cables. Module 2 hybrid is off screen**




Tests with L0 prototype



- **Floating CF picks up noise**
- **Induces noise in Silicon**
- **Regions with only the cable or only one sensor bonded have less pickup**

Once the CF is grounded the pickup is much less

More studies will proceed with new modules and CF structure





Schedule/Plans

- ◆ November:
 - ➔ Finish testing of assembled modules
 - ➔ Build a full stave (both sides)
 - ➔ Study noise and pickup with various grounding and shield configurations
- ◆ Dec.- Jan.:
 - ➔ Build more staves (~10)
 - ➔ Build 5 L0 modules
 - ➔ Build barrel and setup for stave installation
- ◆ Jan.-Feb:
 - ➔ Install completed staves and test in barrel
 - ➔ Install L0 modules on CF structure and test
- ◆ March-May
 - ➔ Test barrel and L0 separately
 - ➔ Install L0 in barrel and test together
 - ➔ Write papers



Remaining M&S Costs

Documentation, SVX4 close-out	\$21,130.00
Bus Cable Manufacturing	\$6,000.00
Data-JPC Fabrication	\$1,000.00
Power-JPC Fabrication	\$4,000.00
Setup new DAQ stands at FNAL	\$4,000.00
Barrel test box	\$7,500.00
Miscellaneous fixtures and modifications	\$10,000.00
Post processing (9 wafers)	\$4,000.00
Probe Station Maintenance	\$2,500.00
L0 protoype system test	\$2,000.00
Preparing 2nd CF Support Structure	\$2,000.00
L0 detector system test (5 modules)	\$4,000.00
Combined Outer/L0 System Test	\$5,000.00
Stave stability test	\$2,000.00

Total ~ 100k\$ (75k\$ + overhead)