



The Run IIb CDF Detector Project


Patrick T. Lukens

Fermilab

12 August 2002



CDF for Run II



- The current detector was designed/built based on Run IIa specifications:
 - Maximum instantaneous luminosity of $2 \times 10^{32} \text{cm}^{-2} \text{s}^{-1}$.
 - Integrated luminosity of 2 fb^{-1} .
 - Operation with 396 ns and 132 ns bunch spacing.
- As in Run I, CDF's strength lies in its tracking system
 - Good momentum precision
 - Good vertex precision – b hadron identification



The Run IIb Specifications

- Operating conditions for Run IIb:
 - Maximum instantaneous luminosity of $4-5 \times 10^{32} \text{cm}^{-2} \text{s}^{-1}$.
 - Integrated luminosity of 15fb^{-1} .
- Not all portions of the detector can operate effectively in these conditions
 - Integrated luminosity results in radiation damage of the tracking system.
 - Instantaneous luminosity results in high occupancy events and requires increase data acquisition bandwidth.
- The Run IIb project consists of replacements for key elements needed for the Higgs search and maintenance of the high P_T program.




Run IIa silicon system

- Radiation damage tests and rate measurements allow us to predict the lifetime of the SVXII.

| Layer | Lifetime (fb^{-1}) |
|-------|-------------------------------|
| 00 | 7.4 |
| 0 | 4.3 |
| 1 | 8.5 |
| 2 | 10.7 |
| 3 | 23 |
| 4 | 14 |

- We are forced to replace the inner layers.




Silicon detector end view



Instantaneous Luminosity

- The instantaneous luminosity of run IIb produces
 - Occupancy problems - fake triggers and overlapping events
 - An issue for the preshower and track trigger
 - Data collection rate problems - handling the data volume/rate
 - Impacts the data acquisition, and exceeds the capacity of our TDCs






CDF's Run IIb Projects

- We have developed a program of upgrades to the current system that are required to maintain CDF as a viable Higgs search experiment for Run IIb:
 - Replacement Silicon Detector
 - Upgrades to the Calorimeter
 - Upgrades to the Data Acquisition and Trigger system
- This program has been presented to the Physics Advisory Committee, and received their approval.



Run IIb silicon system

- New detector is designed for quick construction
- A basic module - the “stave” will be built
- This structure will populate most of the detector volume
- This gives the advantage of fewer parts than the current detector




Silicon detector end view



Silicon Installation

- Silicon detector replacement
 - Space constraints require removal of the central detector from the collision hall
 - This requires 14 weeks (round trip).
- Time constraints force a complete replacement of SVXII.
 - Partial replacement would also be very risky.


ISL and SVXII positioned for installation (Jan. 2001)





Preshower Replacement

- The preshower replacement will take the place of existing CPR.
- One of the last pieces of gas calorimetry (most replaced for Run IIa)
 - Replacement uses scintillator
 - Optical fiber readout, with 16 channel phototubes
 - Same readout/phototubes used in the plug calorimeter shower maximum detector



An early CPR2 prototype



Calorimeter Timing

- This project will add timing information to the electromagnetic calorimeters
- Strengthens the overall quality of the data
- Will suppress fake photons, due to out of time signals
 - Cosmic rays, halo
- These are significant backgrounds to SUSY searches.



Data Acquisition

- Our current data acquisition is specified to operate at a level 2 trigger accept rate of 300 Hz.
- The Run IIb high P_T program requires at least 750 Hz capability.
- Upgrades are needed to
 - Event builder switch – collects data from many sources, forms an event, and moves it to the level 3 computers
 - Time to digital converters – TDCs used for the COT have an inherent readout limit at about 300 Hz.



Triggers

- The high event occupancy for Run IIb drives up the rate of fake triggers in the tracking system
 - Fast track trigger (XFT) requires upgrading
- The duration of the run motivates the need for maintenance of processors that will become obsolete, and uneconomical to maintain
 - Level 2 decision crate
 - Level 3 processors (PCs)
 - High occupancy will also drives a need for greater processing power




Installation

- The project does not include installation of the detector components in its scope.
 - Project completion is decoupled from Tevatron operations.
 - In this strategy, project completion can be independent of Run IIa operations.
- However, we will manage the installation activities.
 - Resource loaded schedule will be maintained for it.
- We currently plan a 34 week shutdown for the silicon replacement.
 - Installations for preshower and the various cabling tasks occur within that period.



Run IIb Organization





Resource Loaded Schedules

- Resource loaded schedules have been created for each subproject.
- All M&S, R&D, and labor costs have been derived from the schedules.
- Labor rates originate from Particle Physics Division
 - Special category created for Silicon Facility labor
- Some labor is contained in M&S costs
 - Silicon work at LBL
 - Preshower construction at Argonne



Schedules

- The silicon detector sets the critical path for the project.
- A base estimate schedule has been written, which the Level 2 managers feel accurately reflects the length of time it will take to build the detector
 - No explicit contingency is included in this base schedule.
 - This is the schedule used to manage the project
- Milestones are placed at the end of significant tasks in the resource loaded schedules.



Schedule Contingency

- A hierarchy of milestones has been established and implemented in the silicon schedule.
 - Level 4 - ~100, used by the project managers
 - Reportable to CDF Run IIb Project Manager
 - Level 3 - A subset corresponding to significant events
 - Level 2 - Copies of the Level 3 milestones, with schedule contingency added.
 - Reportable to the Directorate and DOE Run II Project Manager
 - Level 1 - A subset of the Level 2 milestones, with additional contingency added.
 - Reportable to DOE headquarters



Schedule

- This approach to the schedule strategy gives us a schedule to use for project management
 - Defined by the Level 3/4 milestones, this is the schedule we plan to follow.
- Schedule contingency is then explicitly inserted before the Level 1 and 2 milestones.
- We plan to treat schedule contingency as we do cost contingency
 - It will be held in reserve, and used through the project as required.
 - Use will require a formal change control process.



Cost Contingency

- Our cost contingency is calculated for the lowest level tasks in the schedules.
- Guidelines are as follows:

| Description | Level |
|---------------------------------------------------|-------|
| Item is Complete | 0% |
| Purchase order has been placed | 10% |
| Engineering estimate, based on vendor information | 30% |
| Physicist estimate, based on conceptual design | 50% |
| Estimate based on experience | 100% |



Risk Analysis

- Risk is minimized in the basic design of the subprojects in every way possible
 - Reuse of familiar technologies and techniques
 - Conservatism in the designs - no aggressive performance specifications
 - Ample cost and schedule allocated - contingency added where appropriate.
- Analysis of risk to the current plan has been performed along the lines of a formalism described in the Project Management Body of Knowledge.



Risk Analysis

- Two factors are estimated in the risk analysis
 - Impact factor - severity of impact of an item's substandard performance on the project (cost overrun, schedule slip, technical performance, etc.)
 - Probability of occurrence - the likelihood that substandard performance will occur
- The product of these gives a risk factor.
- Mitigation is considered for items with a high risk factor (> 0.15).



Impact Factors

| | Very Low Risk 0.05 | Low Risk 0.1 | Moderate Risk 0.2 | High Risk 0.4 | Very High Risk 0.8 |
|----------------------------|----------------------------------------------------|-----------------------------------------------------------|------------------------------------------------------------|--------------------------------------------------------------------------|-------------------------------------------------------------------|
| Cost Objective | Insignificant cost increase | < 5% Cost increase | 5-10% Cost increase | 10-20% Cost increase | > 20% Cost increase |
| Schedule Objective | Insignificant schedule slippage | Schedule slippage < 5% | Overall Project slippage 5-10% | Overall Project slippage 10-20% | Overall Project slippage > 20% |
| Scope Objective | Scope decrease barely noticeable | Minor areas of scope affected | Major areas of scope affected | Project scope reduction unacceptable for physics objectives | Scope of project effectively useless for mission |
| Technical Objective | Technical degradation of project barely noticeable | Technical performance of final product minimally affected | Technical performance of final product moderately affected | Degradation of technical performance unacceptable for physics objectives | Technical performance of end item effectively useless for mission |



Risk Analysis

- The impact table is adapted to reflect meaningful situations with respect to the subprojects.
- Risk analyses are performed by the Level 2 managers
 - An separate analysis of our riskiest project (silicon) has also been written by the Run Ila silicon manager.
- High risk items are mitigated
 - Cost or schedule contingency
 - Alternative strategies (additional vendors, preproduction pieces, etc.).



Cost Estimates

- Currently, all cost estimates are obtained by extracting the resource loaded schedule information into a spreadsheet.
- Indirect costs and escalation are then applied to obtain total cost estimates.
- We are working towards a more sophisticated approach - direct loading of the schedule resources into the Cobra financial package.



Project Tracking

- The Cobra financial package will provide a more accurate estimator for total costs
 - Indirect charges, labor rates, handled better
 - Timing changes handled correctly (i.e., purchase slips into another year and indirects are adjusted)
- Most importantly, it also takes input from the general ledger for comparison to our schedules.
- This is the tool which will be used to calculate earned value, for tracking the project progress.



Cobra Status

- The overhead for interfacing Project files and Cobra is considerable.
 - The logical structure of the schedule is affected.
 - We are discovering this as we go along (no examples to follow).
- However, we have successfully loaded the silicon detector schedule (our largest by far) into Cobra.
 - Sample reports are available
- Other schedules will follow soon.
- Interface with the general ledger is in progress.



Total Cost by Subproject

| | 2002 | 2003 | 2004 | 2005 | 2006 | Totals |
|----------------|--------------|---------------|---------------|--------------|-------------|---------------|
| Silicon | \$ 1,308,372 | \$ 4,452,453 | \$ 5,585,615 | \$ 749,269 | \$ - | \$ 12,095,709 |
| Calorimeter | \$ 70,141 | \$ 642,468 | \$ 333,244 | \$ - | \$ - | \$ 1,045,853 |
| DAQ/Trigger | \$ 147,257 | \$ 1,487,722 | \$ 3,085,666 | \$ 220,467 | \$ - | \$ 4,941,113 |
| Administration | \$ 211,287 | \$ 261,383 | \$ 266,802 | \$ 263,927 | \$ 69,929 | \$ 1,073,327 |
| Sub-Total | \$ 1,737,057 | \$ 6,844,026 | \$ 9,271,327 | \$ 1,233,663 | \$ 69,929 | \$ 19,156,003 |
| Contingency | \$ 531,434 | \$ 3,650,900 | \$ 4,381,666 | \$ 588,931 | \$ 34,964 | \$ 9,187,896 |
| Total | \$ 2,268,491 | \$ 10,494,926 | \$ 13,652,993 | \$ 1,822,594 | \$ 104,893 | \$ 28,343,898 |


Total costs in \$AY

- Our overall contingency is 47%.
- Additional resources are required in the form of contributed labor.
 - Physicists are not considered part of the project cost.
 - This labor is included in the schedules.



Cost Breakdown


CDF Run IIb Cost Breakdown





Labor Required


Manpower Estimates





R&D Required

Remaining R&D



G&A is not included here.



Funding Required

| | 2002 | 2003 | 2004 | 2005 | 2006 | Totals |
|----------------------|---------------------|----------------------|----------------------|---------------------|-------------------|----------------------|
| US - M&S | \$ 764,393 | \$ 4,726,795 | \$ 8,726,735 | \$ 700,533 | \$ 82,950 | \$ 15,001,406 |
| US - Labor | \$ 801,019 | \$ 2,423,477 | \$ 2,354,451 | \$ 779,669 | \$ 6,336 | \$ 6,364,951 |
| US - G&A | \$ 359,185 | \$ 1,487,456 | \$ 2,131,429 | \$ 342,392 | \$ 15,607 | \$ 4,336,069 |
| US - Total | \$ 1,924,596 | \$ 8,637,728 | \$ 13,212,614 | \$ 1,822,594 | \$ 104,893 | \$ 25,702,426 |
| Japan | \$ 211,295 | \$ 1,483,118 | \$ 306,925 | \$ - | \$ - | \$ 2,001,338 |
| Italy | \$ 73,000 | \$ 316,619 | \$ 133,454 | \$ - | \$ - | \$ 523,073 |
| University | \$ 59,600 | \$ 57,461 | \$ - | \$ - | \$ - | \$ 117,061 |
| Total Funding | \$ 2,268,491 | \$ 10,494,926 | \$ 13,652,993 | \$ 1,822,594 | \$ 104,893 | \$ 28,343,898 |

Total funds required in \$AY

- These are the funds required to cover M&S purchases and nonscientific labor.
- This profile follows the schedule we will use for management.
 - Without schedule contingency



Summary

- We have developed a well focused program to upgrade CDF for the Run IIb era.
- This project will maintain the high P_T physics program, and enable CDF to continue as a Higgs search experiment until the LHC era begins.
- The window of opportunity for Run IIb requires the detector upgrades to begin soon.
 - Major purchases for silicon are scheduled for November.



Conclusion

- The CDF collaboration has a strong history of supporting the experiment, and has made good use of the data.
 - Recent Spokesmen's poll indicated ample scientific manpower will be available for the project.
- We are fully committed to proceeding with the Run IIb CDF detector project, and we are eager to get going.